SINGLE DUCT & REHEAT TERMINAL SCEHDULE -3RD FLOOR

UNIT MARK	MANUFACTURER	MODEL	INLET SIZE	CFM MAX	CFM MIN	CFM HEAT	COIL ROWS	GPM	3 WAY VALVE	CO2 SENSOR	OCC SENSOR	REMARKS
VAV-1_RH-2-RTU1&2-1	TITUS	DESV	14	1,600	320	800	3	2.1	-	-	X	-
VAV-2_RH-2-RTU3-2	TITUS	DESV	14	1,865	375	935	3	2.2	-	-	X	-
VAV-3_RH-2-RTU3-3	TITUS	DESV	6	210	45	105	2	0.8	-	-	X	-
VAV-4_RH-2-RTU3-4	TITUS	DESV	12	1,265	570	635	3	1.7	-	X	X	-
VAV-5_RH-2-RTU3-5	TITUS	DESV	10	870	450	450	3	1.7	-	X	X	-
VAV-6_RH-2-RTU3-6	TITUS	DESV	6	110	45	55	2	0.8	-	-	X	-
VAV-7_RH-2-RTU4&5-7	TITUS	DESV	8	540	110	270	2	2.2	-	-	X	-
VAV-8_RH-2-RTU4&5-8	TITUS	DESV	6	110	45	55	2	0.8	-	-	X	-
VAV-9_RH-2-RTU4&5-9	TITUS	DESV	6	330	240	240	3	0.8	-	X	X	-
VAV-10_RH-2-RTU4&5-10	TITUS	DESV	8	370	240	240	2	1.4	-	X	X	-
VAV-11_RH-2-RTU4&5-11	TITUS	DESV	12	1,330	265	665	3	1.9	-	-	-	-
VAV-12_RH-2-RTU4&5-12	TITUS	DESV	12	1,460	290	730	3	2	-	-	-	-
VAV-13_RH-2-RTU4&5-13	TITUS	DESV	12	1,365	275	685	3	1.9	-	X	X	-
VAV-14_RH-2-RTU4&5-14	TITUS	DESV	14	1,680	335	840	3	2.1	-	-	X	-
VAV-15_RH-2-RTU3-15	TITUS	DESV	10	695	140	350	2	2.3	-	-	X	-
VAV-16_RH-2-RTU3-16	TITUS	DESV	12	1,150	230	575	3	1.7	-	-	X	-
VAV-17_RH-2-RTU1&2-17	TITUS	DESV	14	1,765	355	885	3	2.1	-	-	X	-
VAV-18_RH-2-RTU1&2-18	TITUS	DESV	6	310	180	180	2	1.3	-	X	X	-
VAV-19_RH-2-RTU1&2-19	TITUS	DESV	8	585	270	295	3	1.3	-	X	X	-
VAV-20_RH-2-RTU1&2-20	TITUS	DESV	10	800	165	400	3	1.7	-	-	X	-
VAV-21_RH-2-RTU1&2-21	TITUS	DESV	6	275	55	140	2	0.9	-	-	X	-
VAV-22_RH-2-RTU1&2-22	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-23_RH-2-RTU1&2-23	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-24_RH-2-RTU1&2-24	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-25_RH-2-RTU1&2-25	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-26_RH-2-RTU1&2-26	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-27_RH-2-RTU1&2-27	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-28_RH-2-RTU1&2-28	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-29_RH-2-RTU1&2-29	TITUS	DESV	14	1,840	720	920	3	2.2	-	X	X	-
VAV-30_RH-2-RTU1&2-30	TITUS	DESV	8	465	360	360	3	1.3	-	X	X	-
VAV-31_RH-2-RTU1&2-31	TITUS	DESV	8	410	120	205	2	1.1	-	-	X	-
VAV-32_RH-2-RTU1&2-32	TITUS	DESV	8	355	90	180	2	0.9	-	-	X	-
VAV-33_RH-2-RTU1&2-33	TITUS	DESV	6	125	60	65	2	0.8	-	-	X	-
VAV-34_RH-2-RTU1&2-34	TITUS	DESV	6	330	300	300	3	1	-	X	-	-
VAV-35_RH-2-RTU3-35	TITUS	DESV	6	80	30	40	2	0.8	-	-	X	-
VAV-36_RH-2-RTU3-36	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-37_RH-2-RTU3-37	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-38_RH-2-RTU3-38	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-39_RH-2-RTU3-39	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-40_RH-2-RTU3-40	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-41_RH-2-RTU3-41	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-42_RH-2-RTU3-42	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-43_RH-2-RTU3-43	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-44_RH-2-RTU3-44	TITUS	DESV	14	1,880	690	940	3	2.2	-	X	X	-
VAV-45_RH-2-RTU3-45	TITUS	DESV	6	210	210	210	2	2.2	-	X	-	-
VAV-46_RH-2-RTU0-46	TITUS	DESV	6	295	240	240	3	0.8	-	X	X	-
VAV-47_RH-2-RTU3-47	TITUS	DESV	6	170	60	85	2	0.8	-	-	X	-
VAV-48_RH-2-RTU3-48	TITUS	DESV	6	205	75	105	2	0.8	-	-	X	-
VAV-49_RH-2-RTU3-49	TITUS	DESV	6	225	90	115	2	0.8	-	-	X	-
VAV-50_RH-2-RTU3-50	TITUS	DESV	10	1,025	450	515	3	1.7	-	X	X	-
VAV-51_RH-2-RTU3-51	TITUS	DESV	6	175	60	90	2	0.8	-	-	X	-
VAV-52_RH-2-RTU3-52	TITUS	DESV	12	1,245	250	625	3	1.7	-	-	X	-
VAV-53_RH-2-RTU3-53	TITUS	DESV	6	145	60	75	2	0.8	-	-	X	-
VAV-54_RH-2-RTU4&5-54	TITUS	DESV	6	225	75	115	2	0.8	-	-	X	-
VAV-55_RH-2-RTU4&5-55	TITUS	DESV	6	305	105	155	2	1	-	-	X	-
VAV-56_RH-2-RTU4&5-56	TITUS	DESV	8	400	240	240	2	1.4	-	X	X	-
VAV-57_RH-2-RTU4&5-57	TITUS	DESV	8	560	450	450	3	1.8	-	X	-	-
VAV-58_RH-2-RTU4&5-58	TITUS	DESV	14	1,790	600	895	3	2.1	-	X	X	-
VAV-59_RH-2-RTU4&5-59	TITUS	DESV	14	1,790	600	895	3	2.1	-	X	X	-
VAV-60_RH-2-RTU4&5-60	TITUS	DESV	14	1,790	600	895	3	2.1	-	X	X	-
VAV-61_RH-2-RTU4&5-61	TITUS	DESV	14	1,790	600	895	3	2.1	-	X	X	-
VAV-62_RH-2-RTU4&5-62	TITUS	DESV	14	1,790	600	895	3	2.1	-	X	X	-
VAV-63_RH-2-RTU4&5-63	TITUS	DESV	6	195	75	100	2	0.8	-	-	X	-
VAV-64_RH-2-RTU6-64	TITUS	DESV	12	1,335	265	670	3	1.9	-	-	-	-
VAV-65_RH-2-RTU6-65	TITUS	DESV	12	1,335	265	670	3	1.9	-	-	-	-
VAV-66_RH-2-RTU6-66	TITUS	DESV	12	1,335	265	670	3	1.9	-	-	-	-
VAV-67_RH-2-RTU6-67	TITUS	DESV	12	1,465	295	735	3	2	-	-	-	-
VAV-68_CO-2-RTU1&2-68	TITUS	DESV	12	1,335	265	-	-	-	-	-	-	-
VAV-69_CO-2-RTU4&5-69	TITUS	DESV	12	1,335	265	-	-	-	-	-	-	-
VAV-70_RH-2-RTU6-70	TITUS	DESV	10	1,075	215	540	3	1.8	-	-	-	-
VAV-71_CO-2-RTU6-71	TITUS	DESV	10	1,075	215	-	-	-	-	-	-	-

NOTES:
2 WAY CONTROL VALVE UON;
140F ENTERING WATER TEMPERATURE; 55F ENTERING AIR TEMPERATURE; 95F LEAVING AIR TEMPERATURE MAX;
MINIMUMS VAVS CAN BE BALANCED TO PER MANUFACTURER: 6" - 80CFM, 8" - 145CFM , 10" - 230CFM, 12" - 325CFM, 14" - 450CFM, 16" - 580CFM
ALL VAV BOXES TO HAVE CONTROLS ENCLOSURES

SINGLE DUCT & REHEAT TERMINAL SCEHDULE -1ST FLOOR

UNIT MARK	MANUFACTURER	MODEL	INLET SIZE	CFM MAX	CFM MIN	CFM HEAT	COIL ROWS	GPM	3 WAY VALVE	CO2 SENSOR	OCC SENSOR	REMARKS
VAV-1_RH-1-RTU7-1	TITUS	DESV	10	800	160	400	3	1.7	-	-	X	-
VAV-2_RH-1-RTU7-2	TITUS	DESV	10	835	165	420	3	1.7	-	-	X	-
VAV-3_RH-1-RTU7-3	TITUS	DESV	12	1,420	285	710	3	2	-	X	X	-
VAV-4_RH-1-RTU1&2-4	TITUS	DESV	12	1,265	255	635	3	1.7	-	-	X	-
VAV-5_RH-1-RTU1&2-5	TITUS	DESV	8	390	90	195	2	1.1	-	-	-	-
VAV-6_RH-1-RTU1&2-6	TITUS	DESV	10	725	570	570	3	1.9	-	X	X	-
VAV-7_RH-1-RTU1&2-7	TITUS	DESV	8	530	390	390	3	1.5	-	X	X	-
VAV-8_RH-1-RTU1&2-8	TITUS	DESV	10	690	140	345	0	0	-	-	X	-
VAV-9_RH-1-RTU1&2-9	TITUS	DESV	8	570	570	570	3	3.2	-	X	X	-
VAV-10_RH-1-RTU1&2-10	TITUS	DESV	8	570	570	570	3	3.2	-	X	X	-
VAV-11_RH-1-RTU1&2-11	TITUS	DESV	10	930	240	465	3	1.7	-	X	X	-
VAV-12_RH-1-RTU1&2-12	TITUS	DESV	12	1,325	265	665	3	1.9	-	-	X	-
VAV-13_CO-1-RTU4&5-13	TITUS	DESV	14	1,525	305	-	-	-	-	-	X	-
VAV-14_RH-1-RTU4&5-14	TITUS	DESV	12	1,265	255	635	3	1.7	-	-	-	-
VAV-15_RH-1-RTU4&5-15	TITUS	DESV	8	440	360	360	3	1.3	-	X	X	-
VAV-16_RH-1-RTU4&5-16	TITUS	DESV	10	890	570	570	3	1.9	-	X	X	-
VAV-17_RH-1-RTU4&5-17	TITUS	DESV	8	440	240	240	2	1.4	-	X	X	-
VAV-18_RH-1-RTU4&5-18	TITUS	DESV	6	305	60	155	2	1	-	-	X	-
VAV-19_RH-1-RTU4&5-19	TITUS	DESV	10	860	170	430	3	1.7	-	-	X	-
VAV-20_RH-1-RTU4&5-20	TITUS	DESV	10	840	180	420	3	1.7	-	X	X	-
VAV-21_RH-1-RTU4&5-21	TITUS	DESV	14	2,000	400	1000	3	2.4	-	-	X	-
VAV-22_RH-1-RTU4&5-22	TITUS	DESV	12	1,435	285	720	3	2	-	-	X	-
VAV-23_RH-1-RTU4&5-23	TITUS	DESV	12	1,435	285	720	3	2	-	-	X	-
VAV-24_RH-1-RTU1&2-24	TITUS	DESV	10	1,095	220	550	3	1.8	-	-	X	-
VAV-25_RH-1-RTU1&2-25	TITUS	DESV	14	1,815	365	910	3	2.1	-	-	X	-
VAV-26_RH-1-RTU1&2-26	TITUS	DESV	8	605	120	305	3	1.3	-	-	-	-
VAV-27_RH-1-RTU1&2-27	TITUS	DESV	14	1,655	330	830	3	2.1	-	-	-	-
VAV-28_RH-1-RTU1&2-28	TITUS	DESV	10	1,085	215	545	3	1.8	-	-	-	-
VAV-29_RH-1-RTU1&2-29	TITUS	DESV	10	1,085	215	545	3	1.8	-	-	-	-
VAV-30_RH-1-RTU1&2-30	TITUS	DESV	10	680	135	340	0	0	-	-	-	-
VAV-31_RH-1-RTU1&2-31	TITUS	DESV	6	210	210	210	2	2.2	-	X	-	-
VAV-32_RH-1-RTU7-32	TITUS	DESV	6	150	30	75	2	0.8	-	-	-	-
VAV-33_RH-1-RTU7-33	TITUS	DESV	6	200	75	100	2	0.8	-	-	-	-
VAV-34_RH-1-RTU7-34	TITUS	DESV	6	190	60	95	2	0.8	-	-	-	-
VAV-35_RH-1-RTU1&2-35	TITUS	DESV	8	525	105	265	2	1.7	-	-	-	-
VAV-36_RH-1-RTU1&2-36	TITUS	DESV	12	1,235	385	620	3	1.7	-	-	-	-
VAV-37_CO-1-RTU1&2-37	TITUS	DESV	14	1,780	355	-	-	-	-	-	-	-
VAV-38_CO-1-RTU1&2-38	TITUS	DESV	14	1,780	355	-	-	-	-	-	-	-
VAV-39_CO-1-RTU1&2-39	TITUS	DESV	14	1,780	355	-	-	-	-	-	-	-
VAV-40_CO-1-RTU1&2-40	TITUS	DESV	14	1,780	355	-	-	-	-	-	-	-
VAV-41_CO-1-RTU1&2-41	TITUS	DESV	14	1,780	355	-	-	-	-	-	-	-
VAV-42_CO-1-RTU1&2-42	TITUS	DESV	14	1,780	355	-	-	-	-	-	-	-
VAV-43_CO-1-RTU1&2-43	TITUS	DESV	12	1,315	265	-	-	-	-	-	-	-
VAV-44_CO-1-RTU1&2-44	TITUS	DESV	12	1,315	265	-	-	-	-	-	-	-
VAV-45_CO-1-RTU1&2-45	TITUS	DESV	12	1,315	265	-	-	-	-	-	-	-
VAV-46_RH-1-RTU1&2-46	TITUS	DESV	6	155	60	80	2	0.8	-	-	X	-
VAV-47_RH-1-RTU1&2-47	TITUS	DESV	10	730	145	365	2	2.3	-	-	X	-
VAV-48_CO-1-RTU1&2-48	TITUS	DESV	12	1,285	255	-	-	-	-	-	X	-
VAV-49_CO-1-RTU1&2-49	TITUS	DESV	12	1,360	270	-	-	-	-	-	X	-
VAV-50_CO-1-RTU1&2-50	TITUS	DESV	10	1,035	205	-	-	-	-	-	-	-
VAV-51_CO-1-RTU1&2-51	TITUS	DESV	10	1,035	205	-	-	-	-	-	-	-
VAV-52_RH-1-RTU1&2-52	TITUS	DESV	10	820	270	410	3	1.7	-	X	X	-
VAV-53_RH-1-RTU1&2-53	TITUS	DESV	8	570	570	570	3	3.2	-	X	X	-
VAV-54_RH-1-RTU4&5-54	TITUS	DESV	6	205	75	105	2	0.8	-	-	X	-
VAV-55_RH-1-RTU4&5-55	TITUS	DESV	6	270	105	135	2	0.8	-	-	X	-
VAV-56_RH-1-RTU4&5-56	TITUS	DESV	6	305	180	180	2	1.3	-	X	X	-
VAV-57_CO-1-RTU4&5-57	TITUS	DESV	14	1,635	325	-	-	-	-	-	X	-
VAV-58_CO-1-RTU4&5-58	TITUS	DESV	14	1,635	325	-	-	-	-	-	X	-
VAV-59_CO-1-RTU4&5-59	TITUS	DESV	14	1,635	325	-	-	-	-	-	X	-
VAV-60_CO-1-RTU4&5-60	TITUS	DESV	14	1,635	325	-	-	-	-	-	X	-
VAV-61_CO-1-RTU4&5-61	TITUS	DESV	14	1,635	325	-	-	-	-	-	X	-
VAV-62_RH-1-RTU4&5-62	TITUS	DESV	8	355	240	240	2	1.4	-	X	X	-
VAV-63_RH-1-RTU4&5-63	TITUS	DESV	6	200	60	100	2	0.8	-	-	X	-
VAV-64_RH-1-RTU4&5-64	TITUS	DESV	6	245	75	125	2	0.8	-	-	X	-
VAV-65_RH-1-RTU4&5-65	TITUS	DESV	6	120	45	60	2	0.8	-	-	X	-
VAV-66_RH-1-RTU4&5-66	TITUS	DESV	6	245	60	125	2	0.8	-	-	X	-
VAV-67_RH-1-RTU4&5-67	TITUS	DESV	8	415	240	240	2	1.4	-	X	X	-
VAV-68_RH-1-RTU4&5-68	TITUS	DESV	14	1,960	390	980	3	2.4	-	-	-	-
VAV-69_RH-1-RTU4&5-69	TITUS	DESV	8	570	570	570	3	3.2	-	X	X	-
VAV-70_RH-1-RTU4&5-70	TITUS	DESV	6	275	210	210	2	2.2	-	X	X	-
VAV-71_RH-1-RTU4&5-71	TITUS	DESV	6	215	60	110	2	0.8	-	-	X	-
VAV-72_RH-1-RTU4&5-72	TITUS	DESV	6	300	105	150	2	1	-	-	X	-
VAV-73_RH-1-RTU4&5-73	TITUS	DESV	10	995	200	500	3	1.7	-	-	-	-
VAV-74_RH-1-RTU4&5-74	TITUS	DESV	8	410	360	360	3	1.3	-	X	X	-
VAV-75_RH-1-RTU4&5-75	TITUS	DESV	6	205	180	180	2	1.3	-	X	X	-
VAV-76_RH-1-RTU4&5-76	TITUS	DESV	16	2,115	425	1060	3	3.3	-	-	X	-
VAV-77_CO-1-RTU4&5-77	TITUS	DESV	14	1,720	345	-	-	-	-	-	X	-
VAV-78_CO-1-RTU4&5-78	TITUS	DESV	14	1,720	345	-	-	-	-	-	X	-
VAV-79_CO-1-RTU4&5-79	TITUS	DESV	14	1,720	345	-	-	-	-	-	X	-

NOTES:
2 WAY CONTROL VALVE UON;
140F ENTERING WATER TEMPERATURE; 55F ENTERING AIR TEMPERATURE; 95F LEAVING AIR TEMPERATURE MAX;
MINIMUMS VAVS CAN BE BALANCED TO PER MANUFACTURER: 6" - 80CFM, 8" - 145CFM , 10" - 230CFM, 12" - 325CFM, 14" - 450CFM, 16" - 580CFM
ALL VAV BOXES TO HAVE CONTROLS ENCLOSURES



Reserved for permit stamp

Olson Kundig
159 South Jackson St, Suite 600
Seattle, Washington 98104 USA
+1 206 624 5670 olsonkundig.com

project:
MIDPOINT OFFICE BUILDING 7 RENOVATION
4400 1ST ST.
SAN JOSE CA 95134

CMT
1901 JUNCTION AVE
Tel 408.437.7000
Fax 408.437.7199

"These drawings and specifications have been prepared by CMI for their exclusive use in accord with Sec. 6737.4 of the Professional Engineers Act of the State of California."

principal architect
project manager
drawn by Author
checked by Checker
job no. 20524
date 07/06/2021

revisions:

no. date by

NOT FOR CONSTRUCTION
COUNTY OF SANTA CLARA DEH SUBMITTAL
07/06/2021

EQUIPMENT SCHEDULES (CONT'D)

M1.01