SINGLE DUCT & REHEAT TERMINAL SCEHDULE - 3RD FLOOR

UNIT TAG (FINAL)	MANUFACTURER	MODEL	INLET SIZE	CFM MAX	CFM MIN	CFM HEAT	COIL ROWS	GPM	3 WAY VALVE	CO2 SENSOR	OCC SENSOR	REMARKS
VAV-163_RH-3-ACU-1-163	TITUS	DESV	14	1600	320	800	3	1.5	-	-	-	-
VAV-164_RH-3-ACU-3-164	TITUS	DESV	14	1865	375	935	3	1.8	-	-	-	-
VAV-165_RH-3-ACU-3-165	TITUS	DESV	6	205	45	105	2	0.4	-	-	X	-
VAV-166_RH-3-ACU-3-166	TITUS	DESV	12	1315	265	660	2	2.5	-	-	X	-
VAV-167_RH-3-ACU-3-167	TITUS	DESV	6	215	45	110	2	0.4	-	-	X	-
VAV-168_RH-3-ACU-3-168	TITUS	DESV	6	130	60	65	1	0.5	-	-	X	-
VAV-169_RH-3-ACU-4-169	TITUS	DESV	12	1150	240	575	3	0.7	-	-	-	-
VAV-170_RH-3-ACU-4-170	TITUS	DESV	8	640	240	320	2	1.7	-	-	X	-
VAV-171_RH-3-ACU-4-171	TITUS	DESV	12	1315	265	660	2	2.5	-	-	X	-
VAV-172_RH-3-ACU-4-172	TITUS	DESV	8	355	240	240	2	0.9	-	X	X	-
VAV-173_RH-3-ACU-4-173	TITUS	DESV	6	305	60	155	2	0.7	X	-	-	-
VAV-174_RH-3-ACU-6-174	TITUS	DESV	8	620	270	310	2	1.5	X	-	-	-
VAV-175_RH-3-ACU-6-175	TITUS	DESV	8	405	180	205	2	0.7	-	-	X	-
VAV-176_RH-3-ACU-6-176	TITUS	DESV	12	1490	300	745	3	1.6	-	-	-	-
VAV-177_RH-3-ACU-4-177	TITUS	DESV	14	1680	335	840	2	2.9	-	-	-	-
VAV-178_RH-3-ACU-3-178	TITUS	DESV	10	700	140	350	2	1.4	X	-	-	-
VAV-179_RH-3-ACU-3-179	TITUS	DESV	12	1150	230	575	2	2.2	-	-	-	-
VAV-180_RH-3-ACU-1-180	TITUS	DESV	14	1765	355	885	3	1.6	-	-	-	-
VAV-181_RH-3-ACU-1-181	TITUS	DESV	6	310	180	180	2	0.9	-	-	X	-
VAV-182_RH-3-ACU-1-182	TITUS	DESV	8	585	270	295	2	1.3	X	-	X	-
VAV-183_RH-3-ACU-1-183	TITUS	DESV	10	800	165	400	2	1.6	X	-	X	-
VAV-184_RH-3-ACU-1-184	TITUS	DESV	6	275	55	140	2	0.6	-	-	X	-
VAV-185_RH-3-ACU-1-185	TITUS	DESV	14	1860	690	930	3	1.8	-	-	-	-
VAV-186_RH-3-ACU-1-186	TITUS	DESV	14	1860	370	930	3	1.8	-	-	-	-
VAV-187_RH-3-ACU-1-187	TITUS	DESV	14	1860	370	930	3	1.8	-	-	-	-
VAV-188_RH-3-ACU-1-188	TITUS	DESV	14	1860	370	930	3	1.8	-	-	-	-
VAV-189_RH-3-ACU-1-189	TITUS	DESV	14	1860	370	930	3	1.8	-	-	-	-
VAV-190_RH-3-ACU-1-190	TITUS	DESV	14	1860	370	930	3	1.8	-	-	-	-
VAV-191_RH-3-ACU-1-191	TITUS	DESV	14	1860	370	930	3	1.8	-	-	-	-
VAV-192_RH-3-ACU-1-192	TITUS	DESV	14	1860	370	930	3	1.8	-	-	-	-
VAV-193_RH-3-ACU-1-193	TITUS	DESV	8	465	360	360	2	1.8	-	-	X	-
VAV-194_RH-3-ACU-1-194	TITUS	DESV	8	410	120	205	2	0.7	-	-	X	-
VAV-195_RH-3-ACU-1-195	TITUS	DESV	8	570	570	570	3	2	-	X	X	-
VAV-196_RH-3-ACU-1-196	TITUS	DESV	6	125	60	65	1	0.5	-	-	X	-
VAV-197_RH-3-ACU-1-197	TITUS	DESV	6	330	300	300	2	2.1	-	X	-	-
VAV-198_RH-3-ACU-3-198	TITUS	DESV	6	120	45	60	1	0.4	-	-	X	-
VAV-199_RH-3-ACU-3-199	TITUS	DESV	6	120	45	60	1	0.4	-	-	X	-
VAV-200_RH-3-ACU-3-200	TITUS	DESV	14	1900	420	950	3	1.8	-	-	-	-
VAV-201_RH-3-ACU-3-201	TITUS	DESV	14	1900	420	950	3	1.8	-	-	-	-
VAV-202_RH-3-ACU-3-202	TITUS	DESV	14	1900	420	950	3	1.8	-	-	-	-
VAV-203_RH-3-ACU-3-203	TITUS	DESV	14	1740	420	870	3	1.6	-	-	-	-
VAV-204_RH-3-ACU-3-204	TITUS	DESV	14	2010	420	1005	3	1.9	-	-	-	-
VAV-205_RH-3-ACU-3-205	TITUS	DESV	14	2010	420	1005	3	1.9	-	-	-	-
VAV-206_RH-3-ACU-3-206	TITUS	DESV	14	2010	420	1005	3	1.9	-	-	-	-
VAV-207_RH-3-ACU-3-207	TITUS	DESV	14	1900	420	950	3	1.8	X	-	-	-
VAV-208_RH-3-ACU-3-208	TITUS	DESV	14	1900	420	950	3	1.8	-	-	-	-
VAV-209_RH-3-ACU-3-209	TITUS	DESV	6	210	210	210	2	1.1	-	-	-	-
VAV-210_RH-3-ACU-3-210	TITUS	DESV	6	230	210	210	2	1	-	-	X	-
VAV-211_RH-3-ACU-3-211	TITUS	DESV	6	265	105	135	2	0.6	-	-	X	-
VAV-212_RH-3-ACU-3-212	TITUS	DESV	6	205	75	105	2	0.4	-	-	X	-
VAV-213_RH-3-ACU-3-213	TITUS	DESV	10	695	140	350	2	1.4	-	-	X	-
VAV-214_RH-3-ACU-3-214	TITUS	DESV	8	440	360	360	2	1.8	-	-	X	-
VAV-215_RH-3-ACU-3-215	TITUS	DESV	6	220	180	180	2	0.8	-	-	X	-
VAV-216_RH-3-ACU-3-216	TITUS	DESV	14	1990	480	995	3	1.9	-	-	-	-
VAV-217_RH-3-ACU-3-217	TITUS	DESV	14	1990	480	995	3	1.9	X	-	X	-
VAV-218_RH-3-ACU-4-218	TITUS	DESV	6	275	105	140	2	0.6	-	-	X	-
VAV-219_RH-3-ACU-4-219	TITUS	DESV	6	220	75	110	2	0.4	-	-	X	-
VAV-220_RH-3-ACU-4-220	TITUS	DESV	6	225	75	115	2	0.5	-	-	X	-
VAV-221_RH-3-ACU-4-221	TITUS	DESV	6	305	105	155	2	0.7	-	-	X	-
VAV-222_RH-3-ACU-4-222	TITUS	DESV	8	400	240	240	2	0.9	-	X	X	-
VAV-223_RH-3-ACU-4-223	TITUS	DESV	8	520	330	330	2	1.7	X	-	-	-
VAV-224_RH-3-ACU-4-224	TITUS	DESV	14	1810	420	905	3	1.7	-	-	-	-
VAV-225_RH-3-ACU-4-225	TITUS	DESV	14	1810	420	905	2	3.2	-	-	-	-
VAV-226_RH-3-ACU-4-226	TITUS	DESV	14	1810	420	905	2	3.2	-	-	-	-
VAV-227_RH-3-ACU-4-227	TITUS	DESV	14	1810	420	905	2	3.2	-	-	-	-
VAV-228_RH-3-ACU-4-228	TITUS	DESV	14	1810	420	905	2	3.2	-	-	-	-
VAV-229_RH-3-ACU-4-229	TITUS	DESV	6	310	90	155	2	0.7	-	-	X	-
VAV-230_RH-3-ACU-4-230	TITUS	DESV	6	270	105	135	2	0.6	-	-	-	-
VAV-231_RH-3-ACU-4-231	TITUS	DESV	6	190	60	95	1	1	-	-	-	-
VAV-232_RH-3-ACU-6-232	TITUS	DESV	6	270	90	135	2	0.6	-	-	-	-
VAV-233_RH-3-ACU-4-233	TITUS	DESV	14	1990	540	995	3	1.9	-	-	-	-
VAV-234_RH-3-ACU-4-234	TITUS	DESV	14	1990	400	995	3	1.9	-	-	-	-
VAV-235_RH-3-ACU-4-235	TITUS	DESV	14	1990	400	995	3	1.9	-	-	-	-
VAV-236_RH-3-ACU-4-236	TITUS	DESV	14	1990	400	995	3	1.9	-	-	-	-
VAV-237_RH-3-ACU-6-237	TITUS	DESV	14	1990	400	995	3	1.9	-	-	-	-
VAV-238_RH-3-ACU-6-238	TITUS	DESV	14	1990	400	995	3	1.9	-	-	-	-
VAV-239_RH-3-ACU-6-239	TITUS	DESV	14	1990	400	995	3	1.9	-	-	-	-
VAV-240_CO-3-ACU-1-240	TITUS	DESV	12	1335	265	-	-	-	-	-	-	-
VAV-241_CO-3-ACU-4-241	TITUS	DESV	12	1335	265	-	-	-	-	-	-	-
VAV-242_CO-3-ACU-1-242	TITUS	DESV	8	470	95	-	-	-	-	-	-	-
VAV-243_CO-3-ACU-4-243	TITUS	DESV	10	1005	200	-	-	-	-	-	-	-
VAV-244_CO-3-ACU-3-244	TITUS	DESV	8	400	95	-	-	-	-	-	-	-

NOTES:
1) 2 WAY CONTROL VALVE UON.
2) 140F ENTERING WATER TEMPERATURE; 55F ENTERING AIR TEMPERATURE; 95F LEAVING AIR TEMPERATURE MAX.
3) ALL VAV BOXES TO HAVE CONTROLS ENCLOSURES.
4) TITUS SOUND ATTENUATOR REQUIRED FOR ALL VAV BOXES.

AIR DISTRIBUTION SCHEDULE

UNIT MARK	MANUFACTURER	MODEL	FRAME	DUCT SIZE	REMARKS
CD-1	TITUS	PMC	24"x24"	SEE PLANS	LAY-IN SUPPLY, BORDER TYPE 3, #26 WHITE
CD-2	TITUS	PCS	12"x12"	SEE PLANS	LAY-IN SUPPLY, BORDER TYPE 3, #26 WHITE
SWG-1	TITUS	300RS	SEE PLANS	SEE PLANS	DOUBLE DEFLECTION, BORDER TYPE 1, MILL FINISH
SWG-2	TITUS	350RS	SEE PLANS	SEE PLANS	SIDE WALL RETURN, BORDER TYPE 1, MILL FINISH
SDG-1	TITUS	S300FL	SEE PLANS	SEE PLANS	DUCT MOUNTED SUPPLY, MILL FINISH
SDG-2	TITUS	S300FL	24"x4"	SEE PLANS	DUCT MOUNTED SUPPLY, MILL FINISH
RG-1	TITUS	PMR	24"x24"	SEE PLANS	LAY-IN RETURN, #26 WHITE
RG-2	TITUS	PAR	12"x12"	SEE PLANS	LAY-IN RETURN, BORDER TYPE 3, #26 WHITE
EG-1	TITUS	PMR	24"x24"	SEE PLANS	LAY-IN EXHAUST, BORDER TYPE 3, #26 WHITE
LD-1	TITUS	FL-20	2" SLOT	SEE PLANS	HIGH-THROW, BORDER TYPE 22, #26 WHITE

NOTES:
1) ALL CEILING GRILLES TO HAVE A FLEXIBLE DUCT MAX LENGTH OF 5 FEET WITH INTEGRAL BALANCE DAMPER.
2) ALL SHEET ROCK GRILLES TO USE A RAPID MOUNT FRAME.

SINGLE DUCT & REHEAT TERMINAL SCEHDULE - 2ND FLOOR

UNIT TAG (FINAL)	MANUFACTURER	MODEL	INLET SIZE	CFM MAX	CFM MIN	CFM HEAT	COIL ROWS	GPM	3 WAY VALVE	CO2 SENSOR	OCC SENSOR	REMARKS
VAV-75_RH-2-ACU-1-75	TITUS	DESV	10	1,035	205	520	3	1.3	-	-	-	-
VAV-76_RH-2-ACU-1-76	TITUS	DESV	12	1,470	295	735	3	1.6	-	-	-	-
VAV-77_RH-2-ACU-1-77	TITUS	DESV	14	1,665	335	835	3	1.6	-	-	-	-
VAV-78_RH-2-ACU-1-78	TITUS	DESV	06	295	60	150	2	0.7	-	-	X	-
VAV-79_RH-2-ACU-1-79	TITUS	DESV	14	1,580	315	790	2	2.8	X	-	-	-
VAV-80_RH-2-ACU-4-80	TITUS	DESV	06	310	60	155	2	0.7	X	-	X	-
VAV-81_RH-2-ACU-4-81	TITUS	DESV	06	220	60	110	2	0.5	-	-	X	-
VAV-82_RH-2-ACU-4-82	TITUS	DESV	10	880	175	440	2	2	-	-	-	-
VAV-83_RH-2-ACU-4-83	TITUS	DESV	08	610	120	305	2	1.5	-	-	-	-
VAV-84_RH-2-ACU-4-84	TITUS	DESV	12	1,490	300	745	3	1.6	-	-	-	-
VAV-85_RH-2-ACU-4-85	TITUS	DESV	08	475	240	240	2	1	X	X	X	-
VAV-86_RH-2-ACU-4-86	TITUS	DESV	06	195	60	100	2	2.1	-	-	X	-
VAV-87_RH-2-ACU-4-87	TITUS	DESV	08	435	270	270	2	1.2	X	-	X	-
VAV-88_RH-2-ACU-4-88	TITUS	DESV	08	430	180	215	2	0.8	-	-	X	-
VAV-89_RH-2-ACU-4-89	TITUS	DESV	10	770	155	385	2	1.6	-	-	-	-
VAV-90_RH-2-ACU-4-90	TITUS	DESV	08	440	90	220	2	0.8	-	-	X	-
VAV-91_RH-2-ACU-4-91	TITUS	DESV	10	955	390	480	2	2.7	-	X	X	-
VAV-92_RH-2-ACU-4-92	TITUS	DESV	10	865	180	435	2	2	X	-	X	-
VAV-93_RH-2-ACU-4-93	TITUS	DESV	16	2,025	600	1015	3	2.2	X	-	-	-
VAV-94_RH-2-ACU-4-94	TITUS	DESV	10	980	195	490	2	2.5	-	-	-	-
VAV-95_RH-2-ACU-1-95	TITUS	DESV	14	1,585	315	795	2	2.8	-	-	-	-
VAV-96_RH-2-ACU-1-96	TITUS	DESV	10	735	145	370	2	1.6	-	-	-	-
VAV-97_RH-2-ACU-1-97	TITUS	DESV	12	1,215	245	610	2	2.5	-	-	-	-
VAV-98_RH-2-ACU-1-98	TITUS	DESV	08	400	180	200	2	0.7	-	-	X	-
VAV-99_RH-2-ACU-1-99	TITUS	DESV	08	420	270	270	2	1.2	X	-	X	-
VAV-100_RH-2-ACU-1-100	TITUS	DESV	08	380	240	240	2	1	X	X	X	-
VAV-101_RH-2-ACU-1-101	TITUS	DESV	06	180	60	90	2	2.1	-	-	X	-
VAV-102_RH-2-ACU-1-102	TITUS	DESV	08	360	70	180	2	0.6	-	-	X	-
VAV-103_CO-2-ACU-1-103	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-104_CO-2-ACU-1-104	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-105_CO-2-ACU-1-105	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-106_CO-2-ACU-1-106	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-107_CO-2-ACU-1-107	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-108_CO-2-ACU-1-108	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-109_CO-2-ACU-1-109	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-110_CO-2-ACU-1-110	TITUS	DESV	14	1,890	540	-	-	-	-	-	-	-
VAV-111_CO-2-ACU-1-111	TITUS	DESV	06	220	75	-	-	-	-	-	X	-
VAV-112_RH-2-ACU-1-112	TITUS	DESV	08	360	360	360	2	1.8	-	X	-	-
VAV-113_CO-2-ACU-1-113	TITUS	DESV	06	240	75	-	-	-	-	-	X	-
VAV-114_CO-2-ACU-1-114	TITUS	DESV	08	480	95	-	-	-	-	-	X	-
VAV-115_CO-2-ACU-1-115	TITUS	DESV	08	385	105	-	-	-	-	-	X	-
VAV-116_CO-2-ACU-1-116	TITUS	DESV	08	455	360	-	-	-	-	-	X	-
VAV-117_CO-2-ACU-1-117	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-118_CO-2-ACU-1-118	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-119_CO-2-ACU-1-119	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-120_CO-2-ACU-1-120	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-121_CO-2-ACU-1-121	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-122_CO-2-ACU-1-122	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-123_CO-2-ACU-1-123	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-124_CO-2-ACU-1-124	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-125_CO-2-ACU-1-125	TITUS	DESV	14	1,970	690	-	-	-	-	-	-	-
VAV-126_CO-2-ACU-1-126	TITUS	DESV	06	225	90	-	-	-	-	-	X	-
VAV-127_CO-2-ACU-1-127	TITUS	DESV	06	215	75	-	-	-	-	-	X	-
VAV-128_CO-2-ACU-1-128	TITUS	DESV	06	140	60	-	-	-	-	-	X	-
VAV-129_CO-2-ACU-1-129	TITUS	DESV	06	250	75	-	-	-	-	-	X	-
VAV-130_RH-2-ACU-1-130	TITUS	DESV	06	210	210	210	2	1.1	X	-	-	-
VAV-131_CO-2-ACU-1-131	TITUS	DESV	08	490	180	-	-	-	-	-	X	-
VAV-132_CO-2-ACU-1-132	TITUS	DESV	10	820	360	-	-	-	-	-	X	-
VAV-133_CO-2-ACU-1-133	TITUS	DESV	16	2,025	720	-	-	-	-	-	-	-
VAV-134_CO-2-ACU-4-134	TITUS	DESV	16	2,025	720	-	-	-	-	-	-	-
VAV-135_CO-2-ACU-4-135	TITUS	DESV	06	280	105	-	-	-	-	-	X	-
VAV-136_CO-2-ACU-4-136	TITUS	DESV	06	210	75	-	-	-	-	-	X	-
VAV-137_RH-2-ACU-4-137	TITUS	DESV	10	825	165	415	2	1.8	-	-	X	-
VAV-138_CO-2-ACU-4-138	TITUS	DESV	08	405	240	-	-	-	-	X	X	-
VAV-139_CO-2-ACU-4-139	TITUS	DESV	06	335	105	-	-	-	-	-	X	-
VAV-140_CO-2-ACU-4-140	TITUS	DESV	06	220	75	-	-	-	-	-	X	-
VAV-141_CO-2-ACU-4-141	TITUS	DESV	10	910	390	-	-	-	-	X	X	-
VAV-142_CO-2-ACU-4-142	TITUS	DESV	14	1,800	600	-	-	-	-	-	-	-
VAV-143_CO-2-ACU-4-143	TITUS	DESV	14	1,800	600	-	-	-	-	-	-	-
VAV-144_CO-2-ACU-4-144	TITUS	DESV	14	1,800	600	-	-	-	-	-	-	-
VAV-145_CO-2-ACU-4-145	TITUS	DESV	14	1,800	600	-	-	-	-	-	-	-
VAV-146_CO-2-ACU-4-146	TITUS	DESV	14	1,800	600	-	-	-	-	-	-	-
VAV-147_CO-2-ACU-4-147	TITUS	DESV	06	260	105	-	-	-	-	-	X	-
VAV-148_CO-2-ACU-4-148	TITUS	DESV	08	390	360	-	-	-	-	-	X	-
VAV-149_CO-2-ACU-4-149	TITUS	DESV	06	200	60	-	-	-	-	-	X	-
VAV-150_CO-2-ACU-4-150	TITUS	DESV	06	245	90	-	-	-	-	-	X	-
VAV-151_CO-2-ACU-4-151	TITUS	DESV	10	920	185	-	-	-	-	-	X	-
VAV-152_CO-2-ACU-4-152	TITUS	DESV	08	480	95	-	-	-	-	-	X	-
VAV-153_CO-2-ACU-4-153	TITUS	DESV	14	1,920	690	-	-	-	-	-	-	-
VAV-154_CO-2-ACU-4-154	TITUS	DESV	14	1,920	690	-	-	-	-	-	-	-
VAV-155_CO-2-ACU-4-155	TITUS	DESV	14	1,920	690	-	-	-	-	-	-	-
VAV-156_CO-2-ACU-4-156	TITUS	DESV	14	1,920	690	-	-	-	-	-	-	-
VAV-157_CO-2-ACU-4-157	TITUS	DESV	14	1,920	690	-	-	-	-	-	-	-
VAV-158_CO-2-ACU-4-158	TITUS	DESV	14	1,920	690	-	-	-	-	-	-	-
VAV-159_CO-2-ACU-4-159	TITUS	DESV	14	1,920	690	-	-	-	-	-	-	-
VAV-160_CO-2-ACU-1-160	TITUS	DESV	12	1,335	265	-	-	-	-	-	-	-
VAV-161_CO-2-ACU-4-161	TITUS	DESV	12	1,335	265	-	-	-	-	-	-	-
VAV-162_CO-2-ACU-4-162	TITUS	DESV	8	505	100	-	-		-	-	-	-

NOTES:
1) 2 WAY CONTROL VALVE UON.
2) 140F ENTERING WATER TEMPERATURE; 55F ENTERING AIR TEMPERATURE; 95F LEAVING AIR TEMPERATURE MAX.
3) ALL VAV BOXES TO HAVE CONTROLS ENCLOSURES.
4) TITUS SOUND ATTENUATOR REQUIRED FOR ALL VAV BOXES.

FIRE/SMOKE DAMPER & FIRE DAMPER SCHEDULE

UNIT MARK	MANUFACTURER	MODEL	SLEEVE	SIZE	UL RATING	LINKAGE (°F)	LEAKAGE CLASS	END-SWITCH	VOLT	REMARKS
FSD-1	GREENHECK	FSD-212	20"	SEE PLANS	1.5 HR	165	II	YES	115V-1ϕ	INSTALL PER MFG. INSTRUCTIONS;
FD-1	GREENHECK	FD-150	-	SEE PLANS	1.5 HR	165	-	-	-	INSTALL PER MFG. INSTRUCTIONS;

SINGLE DUCT & REHEAT TERMINAL SCEHDULE - 1ST FLOOR

UNIT TAG (FINAL)	MANUFACTURER	MODEL	INLET SIZE	CFM MAX	CFM MIN	CFM HEAT	COIL ROWS	GPM	3 WAY VALVE	CO2 SENSOR	OCC SENSOR	REMARKS
VAV-1_RH-1-ACU-7-1	TITUS	DESV	6	230	45	115	2	0.5	-	-	X	-
VAV-2_RH-1-ACU-7-2	TITUS	DESV	8	630	125	315	2	1.5	X	-	X	-
VAV-3_RH-1-ACU-7-3	TITUS	DESV	10	855	170	430	2	2	-	-	X	-
VAV-4_RH-1-ACU-7-4	TITUS	DESV	12	1,420	285	710	3	1.5	-	-	-	-
VAV-5_RH-1-ACU-1-5	TITUS	DESV	12	1,175	235	590	2	2.3	-	-	X	-
VAV-6_CO-1-ACU-1-6	TITUS	DESV	8	540	110	-	-	-	-	-	-	-
VAV-7_RH-1-ACU-1-7	TITUS	DESV	8	530	390	390	3	1.1	-	X	X	-
VAV-8_RH-1ACU-1-8	TITUS	DESV	12	1,455	290	730	3	1.6	X	-	X	-
VAV-9_RH-1-ACU-1-9	TITUS	DESV	10	895	750	750	3	2.3	-	X	-	-
VAV-10_RH-1-ACU-1-10	TITUS	DESV	8	570	570	570	3	2	-	X	X	-
VAV-11_RH-1-ACU-1-11	TITUS	DESV	8	600	125	300	2	1.4	-	-	X	-
VAV-12_RH-1-ACU-4-12	TITUS	DESV	12	1,110	480	555	2	2	-	-	X	-
VAV-13_RH-1-ACU-4-13	TITUS	DESV	10	660	130	330	2	2.1	-	-	X	-
VAV-14_RH-1-ACU-4-14	TITUS	DESV	10	795	160	400	2	1.7	X	-	-	-
VAV-15_RH-1-ACU-4-15	TITUS	DESV	8	480	240	240	2	0.9	X	-	-	-
VAV-16_RH-1-ACU-4-16	TITUS	DESV	10	1,090	545	545	3	1.4	-	-	X	-
VAV-17_RH-1-ACU-4-17	TITUS	DESV	14	1,650	825	825	2	2.9	-	-	X	-
VAV-18_RH-1-ACU-4-18	TITUS	DESV	12	1,400	280	700	2	3.4	-	-	X	-
VAV-19_RH-1-ACU-4-19	TITUS	DESV	12	1,500	300	750	3	1.6	X	-	X	-
VAV-20_RH-1-ACU-4-20	TITUS	DESV	10	985	195	495	2	2.6	-	-	X	-
VAV-21_RH-1-ACU-1-21	TITUS	DESV	12	1,210	240	605	2	2.4	-	-	X	-
VAV-22_RH-1-ACU-1-22	TITUS	DESV	12	1,440	290	720	3	1.5	X	-	X	-
VAV-23_CO-1-ACU-1-23	TITUS	DESV	8	610	120	-			-	-	-	-
VAV-24_RH-1-ACU-1-24	TITUS	DESV	12	1,305	260	655	2	2.5	-	-	-	-
VAV-25_RH-1-ACU-1-25	TITUS	DESV	14	1,590	320	795	2	2.7	X	-	-	-
VAV-26_RH-1-ACU-1-26	TITUS	DESV	10	810	160	405	2	1.8	-	-	-	-
VAV-27_RH-1-ACU-1-27	TITUS	DESV	6	210	210	210	2	1.1	-	-	-	-
VAV-28_RH-1-ACU-7-28	TITUS	DESV	6	150	35	75	2	0.2	-	-	-	-
VAV-29_RH-1-ACU-7-29	TITUS	DESV	6	200	75	100	2	0.3	-	-	-	-
VAV-30_RH-1-ACU-1-30	TITUS	DESV	8	525	105	265	2	1.1	-	-	-	-
VAV-31_CO-1-ACU-7-31	TITUS	DESV	6	170	60	-	-	-	-	-	-	-
VAV-32_CO-1-ACU-7-32	TITUS	DESV	8	530	105	-	-	-	-	-	-	-
VAV-33_CO-1-ACU-1-33	TITUS	DESV	8	375	90	-	-	-	-	-	-	-
VAV-34_CO-1-ACU-1-34	TITUS	DESV	6	195	45	-	-	-	-	-	-	-
VAV-35_CO-1-ACU-1-35	TITUS	DESV	6	100	60	-	-	-	-	-	-	-
VAV-36_CO-1-ACU-1-36	TITUS	DESV	12	1,175	235	-	-	-	-	-	-	-
VAV-37_CO-1-ACU-1-37	TITUS	DESV	12	1,475	295	-	-	-	-	-	-	-
VAV-38_CO-1-ACU-1-38	TITUS	DESV	14	1,605	320	-	-	-	-	-	-	-
VAV-39_CO-1-ACU-1-39	TITUS	DESV	14	1,605	320	-	-	-	-	-	-	-
VAV-40_CO-1-ACU-1-40	TITUS	DESV	12	1,270	255	-	-	-	-	-	-	-
VAV-41_CO-1-ACU-1-41	TITUS	DESV	12	1,270	255	-	-	-	-	-	-	-
VAV-42_CO-1-ACU-1-42	TITUS	DESV	8	485	95	-	-	-	-	-	X	-
VAV-43_CO-1-ACU-1-43	TITUS	DESV	10	730	145	-	-	-	-	-	X	-
VAV-44_CO-1-ACU-1-44	TITUS	DESV	12	1,215	245	-	-	-	-	-	-	-
VAV-45_CO-1-ACU-1-45	TITUS	DESV	12	1,215	245	-	-	-	-	-	-	-
VAV-46_CO-1-ACU-1-46	TITUS	DESV	6	160	30	-	-	-	-	-	-	-
VAV-47_CO-1-ACU-1-47	TITUS	DESV	10	800	160	-	-	-	-	-	-	-
VAV-48_CO-1-ACU-1-48	TITUS	DESV	8	450	390	-	-	-	-	X	-	-
VAV-49_CO-1-ACU-4-49	TITUS	DESV	8	420	390	-	-	-	-	X	X	-
VAV-50_CO-1-ACU-4-50	TITUS	DESV	6	315	240	-	-	-	-	-	X	-
VAV-51_CO-1-ACU-4-51	TITUS	DESV	8	430	360	-	-	-	-	-	X	-
VAV-52_CO-1-ACU-4-52	TITUS	DESV	8	570	570	-	-	-	-	X	X	-
VAV-53_CO-1-ACU-4-53	TITUS	DESV	6	340	90	-	-	-	-	-	X	-
VAV-54_CO-1-ACU-4-54	TITUS	DESV	8	395	240	-	-	-	-	X	-	-
VAV-55_CO-1-ACU-4-55	TITUS	DESV	8	395	240	-	-	-	-	X	-	-
VAV-56_CO-1-ACU-4-56	TITUS	DESV	8	375	270	-	-	-	-	-	-	-
VAV-57_CO-1-ACU-4-57	TITUS	DESV	6	135	45	-	-	-	-	-	-	-
VAV-58_CO-1-ACU-4-58	TITUS	DESV	6	135	45	-	-	-	-	-	-	-
VAV-59_CO-1-ACU-4-59	TITUS	DESV	6	280	75	-	-	-	-	-	X	-
VAV-60_CO-1-ACU-4-60	NOT USED											
VAV-61_CO-1-ACU-4-61	TITUS	DESV	8	395	240	-	-	-	-	X	X	-
VAV-62_CO-1-ACU-4-62	NOT USED											
VAV-63_CO-1-ACU-4-63	TITUS	DESV	14	1,790	360	-	-	-	-	-	X	-
VAV-64_CO-1-ACU-4-64	TITUS	DESV	14	2,000	400	-	-	-	-	-	X	-
VAV-65_CO-1-ACU-4-65	TITUS	DESV	14	2,000	400	-	-	-	-	-	-	-
VAV-66_RH-1-ACU-4-66	TITUS	DESV	14	2,000	1060	1060	3	0.9	-	-	X	-
VAV-67_RH-1-ACU-4-67	TITUS	DESV	14	2,000	1060	1060	3	0.9	-	-	X	-
VAV-68_RH-1-ACU-4-68	TITUS	DESV	12	1,200	600	600	2	0.8	-	-	X	-
VAV-69_RH-1-ACU-4-69	TITUS	DESV	12	1,200	600	600	2	0.8	-	-	-	-
VAV-70_RH-1-ACU-4-70	TITUS	DESV	10	715	360	360	2	0.4	-	-	-	-
VAV-71_RH-1-ACU-4-71	TITUS	DESV	8	390	200	200	2	0.2	-	-	X	-
VAV-72_CO-1-ACU-4-72	TITUS	DESV	6	195	45	-	-	-	-	-	X	-
VAV-73_CO-1-ACU-4-73	TITUS	DESV	12	1,335	265	-	-	-	-	-	-	-
VAV-74_RH-1-ACU-4-74	TITUS	DESV	14	1,615	355	810	3	0.6	-	-	-	-

NOTES:
1) 2 WAY CONTROL VALVE UON.
2) 140F ENTERING WATER TEMPERATURE; 55F ENTERING AIR TEMPERATURE; 95F LEAVING AIR TEMPERATURE MAX.
3) ALL VAV BOXES TO HAVE CONTROLS ENCLOSURES.
4) TITUS SOUND ATTENUATOR REQUIRED FOR ALL VAV BOXES.

ANTHONY M. BRUNO
No. M33190

Reserved for permit stamp

Olson Kundig

159 South Jackson St, Suite 600
Seattle, Washington 98104 USA
+1 206 624 5670 olsonkundig.com

project:
MIDPOINT OFFICE BUILDING 7 RENOVATION
4400 1ST ST.
SAN JOSE CA 95134

CMI
1901 JUNCTION AVE
Tel 408.437.7000
Fax 408.437.7199

"These drawings and specifications have been prepared by CMI for their exclusive use in accord with Sec. 6737.4 of the Professional Engineers Act of the State of California."

principal architect
project manager JS
drawn by DP
checked by DK
job no. 20524-000
date 7/27/22

revisions:

no.	date	by

100% CD

CONSTRUCTION DOCUMENTS

7/27/22

EQUIPMENT
SCHEDULES
(CONT'D)

M1.1